# ENGINEERING DEPARTMENT.

## MYSORE RAILWAYS.

*Notification dated 27th June 1931.*

Sealed tenders will be received at the Office of the Executive Engineer, Open Line Division, Mysore Railways Mysore, up to 2 P.M., on Monday the 20th July 1931, from contractors who are willing to do the work of Constructing Waiting Room in continuation of Extension of Station Building, Northern side at Mysore Railway Station.

2. Every tender should be accompanied by an earnest money of Rs. 100 (one-hundred only) which can be paid to the Auditor, Mysore Railways, Mysore, and the receipt thereof enclosed along with the tender.

3. Tenders should be submitted in special forms, which can be obtained from the Executive Engineer, Mysore Railways, Mysore, on payment of Rupee one.

4. Tenders which give rates "as per estimate rates" or "so much per cent above or below estimate rates," will not be considered.

5. The name of the accepted tenderer will be posted on the Notice Board of the Executive Engineer's Office by the end of July 1931 and enquiries regarding the acceptance or rejection of a tender will not be replied.

6. The earnest money of the unsuccessful tenderers will be returned as soon as possible after the tenders are disposed of, while that of the successful tenderer will be retained as part payment towards the security deposit due as per para 7 *infra*.

7. The successful tenderers should deposit with the Auditor, Mysore Railways, before they sign the Schedule Agreement 5 per cent of the value of the work for which the tender is accepted as security for due fulfilment of the terms of the agreement.

8. The final acceptance of the tender will rest with the Superintendent, Way and Works, Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender and who further reserves to himself the right to reject, without assigning any reasons therefor, any or all the tenders.

9. Work should be started within a week of acceptance of tender and completed before 15th September 1931, with a guaranteed monthly rate of progress. The accompanying Schedule gives the approximate quantity of works and this quantity is not guaranteed.

10. The time limit specified in para 9 should be strictly adhered to and any violation of this will render the contractor liable to forfeit his five per cent deposit amount not as a penalty but as ascertained and liquidated damages recoverable accordingly. Any penalty that may be enforced by the Executive Engineer for reasons of delay and unapproved work, will also be levied.

11. Plans and specifications and other details of work to be done are available for inspection in the Executive Engineer's Office, Mysore Railways, Mysore, during the office hours.

12. In all matters of dispute regarding rates, measurement, quality of work, etc., and in all disputes of any kind, the decision of the Superintendent, Way and Works, will be final and legally binding.

*Schedule.*

| Sl. No. | Description of work | Unit | Quantity |
|---|---|---|---|
| 1 | Earth work excavation in all soils ... ... | 1,000 C.ft. | 500 |
| 2 | Concrete in sand mortar ... ... | 100 | 250 |
| 3 | Size stone in sand mortar, with bond stones ... ... (Pillars are partly built) ... ... | C.ft. ,, | 2,200 ... |
| 4 | Burnt stone slabs 6" thick dressed and champhered over basement. | S.ft. | 90 |
| 5 | Burnt stone slabs 4" thick dressed and champhered and rounded over pillars. | ,, | 163 |
| 6 | Burnt stone slabs 6" thick dressed and fixed ... | ,, | 62 |
| 7 | Teakwood truss with 4"x 6" scantlings for 20' span with iron fittings, bolts and nuts, complete including hoisting and fixing and wood oiling. | Each | 6 |
| 8 | Teakwood wrought and put up with woodoiling ... | C.ft. | 133 |
| 9 | Roofing with First Class Mangalore Tiles over Teak reepers 2"x 1" and chunam borders complete (tiles will be supplied Departmentally in P. W. Inspector's Office compound). | Sqr. | 31·20 |
| 10 | Ridge tiles set in mortar (tiles will be supplied in P. W. Inspector's Office compound). | R.ft. | 60 |
| 11 | Teakwood Eave board with painting as existing ... | ,, | 120 |

| Sl. No. | Description of work | Unit | Quantity |
|---|---|---|---|
| 12 | Chunam plastering to stone wall ... ... | Sqr. | 23·40 |
| 13 | Cement Pointing ... ... | " | 22·20 |
| 14 | Flooring with 2½" Cuddapah slabs over 3" concrete and cement pointing (Slabs will be supplied Departmentally near Lamp House at Mysore Station). | " | 19·0 |
| 15 | Stone arch dressed with centering charges, complete ... | 100 C.ft. | 239 |
| 16 | Drilling holes in burnt stone slabs to fix C. I. varandah pillars. | Each | 20 |
| 17 | Hoisting, fixing and assembling with bolts and nuts C. I. columns (columns will be supplied Departmentally). | " | 5 |
| 18 | Fixing C. I. Gate, 7 ' wide (supplied Departmentally) ... | " | 2 |
| 19 | Dressing quoins ... ... ... | R.ft. | 90 |
| 20 | Cutting, conveying, hoisting and fixing 60 lbs. rails for ridge and purlin, supplied Departmentally. | " | 180. |
| 21 | Clearing site, levelling ground and forming surface ... | 100 S.ft. | 2,500 |
| 22 | White washing 2 coats ... ... ... | Sqr. | 23·40 |
| 23 | Cement concrete below truss of verandah over front wall 1:2:4 proportion. | C.ft. | 7·0 |

*N.B.*—Specification for work will be according to Marryat's Hand-Book.

V. RAMANJALU NAIDU,
*Executive Engineer.*

## KADUR DIVISION.

*Abstract Notification dated* 17—19*th June* 1931.

The attention of the public is invited to the grass lease notification in the several plantations of this Division published on pages 643 and 644 of the *Mysore Gazette*, Part VI, dated 25th June 1931.

S. VENKATAVARADIENGAR,
*District Forest Officer.*

## BANGALORE DIVISION.

*Abstract Notification dated* 20*th June* 1931.

The attention of the public is invited to the detailed Notification No. 644 and 645 dated 25th June 1931, published on pages 644 and 645 Part VI of the *Mysore Gazette*, dated 25th June 1931, calling for tenders for restoring Veerasagara Tank, Reg. No. 116 of Magady Taluk.

The last date for receipt of tenders is 15th July 1931 and the earnest money to be deposited Rs. 150.

---

*Abstract Notification dated* 20*th June* 1931.

The attention of the public is drawn to the notification No....., dated 17th June 1931, published on page 645 and 646, Part VI of the *Mysore Gazette*, dated 25th June 1931, calling for the tenders for the improving of Matenahalli Minor Tank, Reg. No. 254 of Hosakote Taluk.

The last date for receipt of tender is 15th July 1931 and the earnest money required is Rs. 150.

N. G. KRISHNA IYENGAR,
*Executive Engineer.*

## KOLAR DIVISION.

*Notice.*

Attention is invited to the publication of notice calling for tenders for Madras-Cannanore road, Bangalore-Bellary road and Kolar Gold Field State Fund road published in the *Mysore Gazette*, dated 25th June 1931, Part VI, pages 647 and 648. Last date of submission of tender is 20th July 1931, 2 P.M.

---

*Notice.*

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part VI, page 622, for tenders for increasing the capacity of Pombarahalli Bylakere, Registered No. 770 of Mulbagal Taluk, Kolar District.

H. R. VENKATASUBBA RAO,
*Executive Engineer.*